



SECTION A
SCALE: H 1:500, V 1:100. DATUM: 65.000



Chainage	0.000	10.000	20.000	30.000	40.000	50.000	60.000	70.000	80.000	90.000	100.000	110.000	120.000	130.000	140.000	150.000	160.000	170.000	180.000	190.000	200.000	210.000	218.818
Proposed Levels	66.802	67.135	67.370	67.498	67.654	67.842	67.959	68.061	68.108	68.253	68.362	68.440	68.485	68.586	68.733	68.836	68.940	69.085	69.139	69.209	69.353	69.486	69.522
Pond Levels		66.656	66.656	66.656	66.656	66.656	66.656	66.656	66.656	66.656	66.656	66.656	66.656	66.656	66.656	66.656	66.656	66.656	66.656	66.656	66.656	66.733	66.733

SECTION B
SCALE: H 1:500, V 1:100. DATUM: 65.000



Chainage	0.000	10.000	20.000	27.293
Proposed Levels	68.819	69.049	68.879	68.789
Pond Levels		68.231	68.028	

- NOTES:**
- DRAWINGS ARE PREPARED TO SUPPORT DETAILED PLANNING APPLICATION FOR THE STRATEGIC HIGHWAY INFRASTRUCTURE ASSOCIATED WITH MILTON KEYNES EAST (MKE) DEVELOPMENT.
 - ALL DIMENSIONS ARE IN METRES UNLESS OTHERWISE STATED.
 - THIS DRAWING SHOULD BE READ IN CONJUNCTION WITH ALL RELEVANT DOCUMENTATION, DRAWINGS AND STANDARD DETAILS.
 - THIS DRAWING IS NOT TO BE REPRODUCED IN ANY PART OF FORM WITHOUT PRIOR CONSENT FROM WSP UK LIMITED, ALL COPY RIGHT RESERVED.
 - DO NOT SCALE FROM THIS DRAWING, IF IN DOUBT CONTACT WSP UK LIMITED.
 - CONFLICTING INFORMATION SHOWN ON THE ENGINEER'S DRAWINGS OR DISCREPANCIES BETWEEN THE INFORMATION GIVEN BY THE ENGINEER AND THAT PROVIDED BY OTHERS MUST BE REFERRED TO THE ENGINEER BEFORE THE WORKS COMMENCE.
 - THE MILTON KEYNES HIGHWAY BOUNDARY IS TAKEN FROM INTERACTIVE HIGHWAY BOUNDARY MAPPING FOUND ON THE MILTON KEYNES COUNCIL'S WEBSITE.
 - TOPOGRAPHICAL INFORMATION PROVIDED BY MK SURVEYS FILE - "28562" ON THE 11/06/2020 AND 3D ENGINEERING SURVEYS FILE - "DES21007_MKE_REV1" ON THE 22/02/2021. WSP CAN NOT ACCEPT RESPONSIBILITY FOR ANY INACCURACIES.
 - ALL DRAINAGE HAS BEEN DESIGNED IN ACCORDANCE WITH THE DCG, DMRB, CIRIA SUDS MANUAL AND MKE GUIDANCE.
 - ALL OUTFALL LEVELS TO BE CONFIRMED ON SITE PRIOR TO CONSTRUCTION
 - SURFACE WATER RUNOFF IS RESTRICTED TO 4L/S/IMPERMEABLE HECTARE. FOR FURTHER DETAILS OF VORTEX CONTROLS USED AND DISCHARGE RATES PLEASE REFER TOT THE ACCOMPANYING CALCULATIONS
 - ALL HEADWALLS TO BE ARCHITECTURALLY CLADDED
 - MAINTENANCE ACCESS TO BE ESTABLISHED IN FULL AT DETAILED DESIGN
 - AT DETAILED DESIGN PONDS WILL BE CONSIDERED FOR A PERMANENT WATER BASE IN ORDER TO IMPROVE BIODIVERSITY

KEY:

— PROPOSED MKE TOPOGRAPHY
— PROPOSED POND PROFILE

PO1	10/03/2021	DE	FIRST ISSUE	DSF	SAP
REV	DATE	BY	DESCRIPTION	CHK	APP

DRAWING STATUS: **S0 - WORK IN PROGRESS**

Grosvenor House, 2 Grosvenor Square, Southampton, SO15 2BE, UK
T+ 44 (0) 2380 101 700
wsp.com

CLIENT: **BERKELEY ST JAMES**

ARCHITECT: **JTP / STEPHEN GEORGE AND PARTNERS**

SITE/PROJECT: **MILTON KEYNES EAST**

TITLE: **POND 27A
LONG SECTIONS**

SCALE @ A1: 1:500 CHECKED: DSF APPROVED: SAP

PROJECT NO: 70057521 DESIGNED: DSF DRAWN: DE DATE: November 20

DRAWING No: **MKE-WSP-ZZ-ZZ-C-SK-0555** REV: **P01**

© WSP UK Ltd